

# EXPEDIENT DRAINAGE



# OVERVIEW

- Plan and design adequate drainage
- Types of drainage systems
- Purpose of adequate drainage
- Maintaining a drainage system

# OBJECTIVES

- Terminal Learning Objectives
- Enabling Learning Objectives

# METHOD / MEDIA

- Lecture method
- Power point
- Demonstration
- Practical application

# EVALUATION

- Written exam

# SAFETY / CEASE TRAINING

- Classroom Instruction
  - No safety concerns for this period of instruction
- Inclement weather plan
- Fire exit plan

# QUESTIONS?

- Are there any questions concerning:
  - What will be taught?
  - How it will be taught?
  - How the student will be evaluated?

# SOURCES OF WATER

- Precipitation
- Interception
- Infiltration
- Ground Water



# PRECIPITATION

- Rain Fall
- Snow Fall/Melt
- Humidity

# INTERCEPTION

- Interception is the process of vegetation absorbing the water before it reaches the soil.
- Once the holding capacity of the vegetation has been reached, the soil will then start receiving water.

# INFILTRATION

- Infiltration is the water's ability to penetrate the soil surface. The following factors affect the process of infiltration:
- Vegetation presence or lack thereof.
- Soil type. (some soil types retain water more than others.)
- Slope of terrain.

# GROUND WATER

- Surface water: Surface water is retained in the top soil. (depended upon vegetation and soil type.)
- Sub-surface water: Water that is present below the ground. (water table).
- Capillary water: The water that seeps to the surface.

# QUESTIONS?

- Any questions?
- Questions for you!!

# ESTIMATING WATER RUNOFF

- Methods of estimating water runoff
  - Hasty
  - Field Estimate

# HASTY METHOD

- The hasty method is used when an existing stream crosses or interferes with your construction site.
- Certain measures must be taken to avoid possible water damage to your construction site.
- Using the following formula, we can determine the “Area of Waterway” (AW)

# HASTY METHOD

$$AW = \frac{W1 + W2}{2} \times H$$

AW = Area of the waterway


W1 = Width of the channel  
bottom

W2 = Width at the high water  
mark

H = Height from the bottom to



# HASTY METHOD



# DRAINAGE SAFETY FACTOR

$$ADES = 2AW$$

ADES = Design cross section

2 = Safety Factor

AW = Area of the waterway that was previously computed

# EXAMPLE # 1

$$\frac{7 + 9}{2} \times 4 = 32 \text{ Sqft (AW)}$$

$$32 \text{ Sqft} \times 2 = 64 \text{ Sqft (Ades)}$$

## EXAMPLE # 2

$$\frac{5 + 7}{2} \times 3 = 18 \text{ Sqft (AW)}$$

$$18 \text{ Sqft} \times 2 = 36 \text{ Sqft (Ades)}$$

**COMPLETE HANDOUTS 1 &  
2**

**PRACTICAL APPLICATION**

# REVIEW

- Review handouts #1 and #2
- Take a Break

# FIELD ESTIMATE METHOD

- The field estimate method is used to estimate the peak volume of storm water runoff.
- Results of this method are adequate for determining the size of drainage structures for temporary drainage in areas of 100 acres or less.

# FORMULA

$$Q = 2 \times A \times R \times C$$

Q = peak volume of storm water runoff, in cubic feet per second

2 = safety factor (constant)

A = area of drainage basin, in acres

R = design rainfall intensity based on the one hour, two year frequency rainstorm, in inches per hour


C = coefficient representing a ration of runoff to rainfall




# DRAINAGE AREA

- The fastest and most preferred method for determining the size of the drainage area is the stripper method
- The first step is called delineation. (Done on a topographic map)


# LOCATE HILLTOPS IN THE VICINITY OF THE CONSTRUCTION SITE



**DRAW ARROWS THAT FOLLOW THE CONTOUR LINES FROM THE HILLTOP DOWN**




# DRAW LINES FROM HILLTOP TO HILLTOP TO OUTLINE AN AREA






# LOCATE THE LONGEST, STEEPEST GRADIENT WITHIN THE DRAINAGE AREA




**CONTINUING PLAN FOR  
NII ARMY AIRFIELD**  
LOCATION: GIESSEN, GERMANY

DESIGNED BY <i>[Signature]</i>	CHECKED BY <i>[Signature]</i>
DATE 15 May 76	DATE 15 May 76
SCALE 1:50,000	SCALE 1:50,000
PROJECT NO. 10-1470	PROJECT NO. 10-1470



- Measure the length of each line in the drainage area.
- Add all the lengths together
- This is the map area in square inches



- **$2.12'' + 2.62'' + .50'' = 5.25$  square inches**

# CONVERSION (INCHES TO ACRES)

- For a more accurate determination, you can draw the lines  $\frac{1}{4}$ " or  $\frac{1}{2}$ " apart from the base line.
- If  $\frac{1}{4}$ " spacing is used, you must take total length of lines and divide by 4.
- If  $\frac{1}{2}$ " spacing is used, you must take total length of lines and divide by 2.



# CONVERSION (INCHES TO ACRES)

- Determine how many feet are in one inch on the map.

■ Example:            MAP Scale: 1 : 5,000

$$5000 \div 12 = 416.67 \text{ ft.}$$

■ 1 inch on the map is 416.67 ft

# CONVERSION (INCHES TO ACRES)

- Determine how many square feet are in one square inch on the map.

$$416.67^2 = 173,613.88$$

One square inch on a map  
contains 173,613.88 square feet on  
the ground

# CONVERSION (INCHES TO ACRES)

**Total square feet in the drainage area?**

$$5.25'' \times 173,613.88 = 911,472.87 \text{ SqFt}$$

- **Now convert square feet to acres.**

$$911,472.87 \div 43,560 = 20.92 \text{ or}$$

$$A = 21 \text{ acres}$$

# FORMULA

$$Q = 2 \times A \times R \times C$$

$$A = 21$$

$$Q = 2 \times 21 \times R \times C$$


# DEMONSTRATION

- Example on page 6 of the student handout
  - Follow along with the demonstration

# Practical Application

- Perform the Practical Exercise Worksheet #1

# RAINFALL INTENSITY



# RAINFALL INTENSITY

- The Project is in Eastern North Carolina
  - It falls between 1.5 and 2.0, always use the larger number.
- Formula

$$Q = 2 \times 21 \times 2 \times C$$



# RUNOFF COEFFICIENT

- The ratio of runoff to rainfall. The amount of water expected to drain from an area as the result of a specific amount of rainfall.
- It is expressed as a decimal.
- There are three primary factors that affect the percentage;
  - Soil type
  - Surface cover
  - slope

# SOIL TYPE

- Porous soil - A large portion of the soil will infiltrate leading to a smaller runoff coefficient
- Man made surfaces – Like asphalt, concrete, and compacted gravel or macadam will result in a higher runoff coefficient

# SURFACE COVER

- To use table 6-1, you need to understand the following terms
- Without Turf – Is ground that is completely bare
- With Turf – Is ground that is covered with vegetation.
- If the area has some vegetation but is not completely covered, use the higher without turf value

# SLOPE

- As terrain becomes steeper, water flows sooner and more rapidly. This allows less time for infiltration to occur and results in the C value becoming larger for the natural cover or soil categories.

# USCS

- Use the Unified Soil Classification System (USCS) to select the PREDOMINANT soil type.
- This will be needed for the left column of table 6-1 (the next slide).
- If the area is wooded or covered with asphalt, concrete, gravel or macadam simply lookup the “C” value in the left hand column.


# FINDING THE RUNOFF COEFFICIENT

UNIFIED SOIL CLASSIFICATION INCLUDING IDENTIFICATION AND DESCRIPTION											
COARSE GRAINED SOILS More than half materials is larger than No. 200 sieve size (The smallest particle visible to the naked eye)	FIELD IDENTIFICATION PROCEDURES (excluding particles larger than 3 inches and basing fractions on estimated weights)			GROUP SYMBOLS	TYPICAL NAMES	INFORMATION REQUIRED FOR DESCRIBING SOILS	LABORATORY CLASSIFICATION CRITERIA				
	GRAVELS More than half of coarse fraction is larger than No. 4 sieve size (For visual classification, the 1/4" size may be used as equivalent for the No. 4 sieve size)	CLEAN GRAVELS (Little or no fines)	Wide range in grain size and substantial amounts of all intermediate particle sizes	GW	Well graded gravels, gravel-sand mixtures, little or no fines	Give typical name; indicate approximate percentage of sand and gravel, max. size; angularity, surface condition, and hardness of the coarse grains; local or geological name and other pertinent descriptive information, and symbol in parentheses  For undisturbed soils add information on stratification, degree of compactness, cementation, moisture conditions and drainage characteristics  EXAMPLE  <u>Silty sand</u> gravelly, about 20% hard, angular gravel particle $\frac{1}{2}$ - in maximum size; rounded and subangular sand grains coarse to fine; about 15% non-plastic fines with low dry strength; well compacted and moist in place; alluvial sand; (SM)	$C_u = \frac{D_{60}}{D_{10}}$ Greater than 4 $C_c = \frac{(D_{30})^2}{D_{10} \times D_{60}}$ between one and 3				
			Predominantly one size or a range of sizes with same intermediate sizes missing	GP	Poorly graded gravels, gravel-sand mixtures, little or no fines		Not meeting all gradation requirements for GW				
			Non-plastic fines (for identification procedures see ML below)	GM	Silty gravel, poorly graded gravel-sand silt mixtures		Atterberg limits above "A" line with PI greater than 7				
			Plastic fines (for identification procedures see CL below)	GC	Clayey gravels, poorly graded gravel-sand clay mixtures		Atterberg limits below "A" line or PI greater than 7				
	SANDS More than half of coarse fraction is smaller than No. 4 sieve size (For visual classification, the 1/4" size may be used as equivalent for the No. 4 sieve size)	CLEAN SANDS (Little or no fines)	Wide range in grain sizes and substantial amount of all intermediate particle sizes	SW	Well graded sands, gravelly sands, little or no fines		$C_u = \frac{D_{60}}{D_{10}}$ Greater than 6 $C_c = \frac{(D_{30})^2}{D_{10} \times D_{60}}$ between one and 3				
			Predominantly one size or a range of sizes with some intermediate sizes missing	SP	Poorly graded sand, gravelly sands, little or no fines			Not meeting all gradation requirements for SW			
			Non-plastic fines (for identification procedures see CL below)	SM	Silty sand, poorly graded sand-silt mixtures			Atterberg limits below "A" line or PI less than 4			
			Plastic fines (for identification procedures see CL below)	SC	Clayey sand, poorly graded sand-clay mixtures			Atterberg limits above "A" line with PI greater than 7			
	FINE GRAINED SOILS More than half materials is smaller than No. 200 sieve size (The No. 200 sieve size is about the smallest particle visible to the naked eye)	IDENTIFICATION PROCEDURES ON FRACTION SMALLER THAN NO. 40 SIEVE SIZE									
SILTS AND CLAYS Liquid limit less than 50		DRY STRENGTH (CRUSHING CHARACTERISTICS)	DILATANCY (REACTION TO SHAKING)	TOUGHNESS (CONSISTENCY NEAR PLASTIC LIMIT)				Give typical name; indicate degree and character of plasticity, amount and maximum size of coarse grains, color in wet condition, odor, if any, local or geologic name, and other pertinent descriptive information, and symbol in parentheses  For undisturbed soils add information on structure, stratification, consistency in undisturbed and remolded states, moisture and drainage conditions  EXAMPLE:  Clayey silt, brown, slightly plastic; small percentage of fine sand; numerous vertical root holes; firm and dry in place; loess, (ML)			
		None to slight	Quick to slow	None	ML	Inorganic silts and very fine sands, rock flour, silty or clayey fine sand with slight plasticity					
		Medium to high	None to very slow	Medium	OL	Inorganic clays of low to medium plasticity, gravelly clays, sandy clays, silty clays, lean clays					
		Slight to medium	Slow	Slight	MN	Organic silts and organic silt-clays of low plasticity					
SILTS AND CLAYS Liquid limit greater than 50		Slight to medium	Slow to none	Slight to medium	OL	Inorganic silt, micaceous or diatomaceous fine sandy or silty soils, elastic silts					
		High to very high	None	High	CH	Inorganic clays of high organic plasticity					
		Medium to high	None to very slow	Slight to medium	OH	Organic clays of medium to high plasticity					
		HIGHLY ORGANIC SOILS			Readily identified by color, odor, spongy feel and frequently by fibrous texture	Pt	Peat and other organic soils				

Use grain size curve in identifying the fractions as given under field identification

Determine percentages of gravel and sand from grain size curve. Depending on percentage of fines (fraction smaller than No. 200 sieve size) coarse grained soils are classified as follows:  
Less than 5%  
More than 5%  
5% to 12%  
12% to 15%  
15% to 20%  
20% to 35%  
35% to 60%  
60% to 85%  
85% to 100%  
GW, GP, SW, SP, GM, GC, SM, SC.  
Borderline cases requiring use of dual symbols

PLASTICITY CHART  
FOR LABORATORY CLASSIFICATION OF FINE GRAINED SOILS




# SLOPE PERCENTAGE

- Identify the slope on the map.
- Find the difference from the top to the bottom of the slope



# SLOPE PERCENTAGE



Elevation B = 181m  
Elevation A = 100m  
Difference in elevation (Vd) = 81m

Horizontal Distance = 4150m

$\frac{Vd}{Hd} \times 100 =$  % of Slope

$$\frac{81}{4150} \times 100 = 1.9\%$$



# TURF/SAFETY

- TURF: If the soil is not covered, determine whether the area is with or without turf
- SAFETY: In all cases where you have more than one possible runoff coefficient, use the highest value

Soil or Cover Classification	C VALUES					
	Slope ≤ 2 %		Slope > 2 & < 7%		Slope ≥ 7%	
	w/turf	w/o turf	w/turf	w/o turf	w/turf	w/o turf
GP, SW, SP	.10	.20	.15	.25	.20	.30
CL, <b>SM</b> d, ML, Pt	.30	<b>.40</b>	.35	.45	.40	.50
GC, SMu, SC DL, CH, OH	.55	.65	.60	.70	.65	.75
Grassed area	.20	.20	.20	.20	.20	.20
Asphalt Pavement		.95		.95		.95
Concrete Pavement		.90		.90		.90
Gravel/macadam		.70		.70		.70

# RUNOFF COEFFICIENT (EXAMPLE)

- Your drainage area is made up of ML soil, with 49% turf and a slope of 2%.
- Looking at Table 6-1 you should come up with 0.40.
- Now in final formula from

$$Q = 2 \times 21 \times 2 \times .40$$

- The Answer :

$$Q = 33.6 \text{ CFS}$$

# **WATERWAY AREA**

- Expedient culvert and ditch design is based on the waterway area.
- The hasty method deals with waterway area.
- The field estimate method deals with peak volume of storm water runoff ( $Q$ ).

# EQUATION

$Q$  = PEAK VOLUME OF STORM WATER RUNOFF

$V$  = VELOCITY OF WATER, IN FEET PER SECOND  
(FPS)

$A_w$  = WATERWAY AREA, IN SQUARE FEET

$$Q = VA_w$$

# EQUATION

- For expedient purposes, you will always use a velocity of 4 fps for design of expedient drainage structures.
- Example
  - $Q = V \times A_w$  (divide both sides by V)
  - The Results are:
    - $Q \div V = A_w$  (Using the previous calculation from your handout of 33.6 cfs)
- Final answer
  - $33.6 \text{ (cfs)} \div 4 \text{ (constant)} = 8.4 \text{ sqft (} A_w \text{, Area of waterway)}$

# SAFETY FACTOR

- As with the hasty method, you rarely design a drainage system to flow completely full.
- You must apply a safety factor (Ades)
- $A_{des} = 2 \times A_w$
- $A_{des} = 2 \times 8.4$
- $A_{des} = 16.8 \text{ sqft}$

# DEMONSTRATION AND PRACTICAL APPLICATION





# QUESTIONS??



# DRAINAGE DITCHES



# TRIANGULAR V-DITCHES

- Triangular (V) ditches are used to move small amounts of water.
  - $Q \leq 60 \text{ cfs}$  or  $A_w \leq 15 \text{ sqft}$


# TRIANGULAR V-DITCHES

- SYMMETRICAL
  - Both sides of the ditch are inclined equally
- NON\_SYMMETRICAL
  - Each side of the ditch are inclined differently
- Ensure the appropriate side-slope ratio is selected to serve its designed purpose.
- If the side walls are too step it invites excessive corrosion and ditch clogging.

# TRIANGULAR V-DITCHES


Ditches have two sloped sides, with each having a respective slope ratio. This is expressed as horizontal feet to vertical feet.

Example: 3 : 1 is a side slope of 3 feet horizontal to a 1 foot vertical.



# TRIANGULAR V-DITCHES

- The sidewall of a ditch located adjacent to the shoulder is called the front slope of the ditch.
- The far slope, called the back slope, is simple an extension of the cut face of the



# TRIANGULAR V-DITCHES FORMULA (DEPTH)

$$D = \sqrt{\frac{Ca \times 2}{X + Y} + 0.5}$$

**D = Ditch depth in feet. Rounded to two decimal places.**

**Ca = Channel area computed previously.**

**X = Horizontal run of the front slope ratio.**

**Y = Horizontal run of the back slope ratio.**

**0.5 = Safety factor constant. (1/2 foot freeboard)**

# TRIANGULAR V-DITCHES FORMULA (WIDTH)


**Ditch Width:  $W = D \times (X + Y)$**

**$W$  = Ditch width in feet. Rounded to two decimal places.**

**$D$  = Ditch depth in feet.**

**$X$  = Front slope ratio.**


**$Y$  = Back slope ratio.**





# EXAMPLE

Using your previous Area of 16.8 sqft and a front slope of 3 : 1 and a back slope 1 : 1, calculate the depth and width of the ditch.


$$D = \frac{16.8}{3+1} + 0.5$$

$$W = D \times (X + Y)$$


$$D = \frac{16.8}{4} + 0.5$$

$$W = 2.55' \times (3 + 1)$$


$$D = 4.2 + 0.5$$

$$W = 2.55 \times 4$$

$$D = 2.05 + 0.5$$

$$W = 10.20'$$

$$D = 2.55'$$

# PRACTICAL APPLICATION

- Triangular Ditch Calculations Worksheet

# TRAPEZOIDAL DITCHES

- Installed for larger runoff requirements, usually 60 cfps / 15 aw or greater.
- The designer of the ditch determines the bottom width based upon the cutting edge of the equipment used.



# FORMULA

**Ditch Depth:  $D = \frac{A_w}{W} + 0.5$**

**D = Ditch Depth in feet. Rounded to two decimals**

**Ca = Channel area in square feet.**

**W = Width of ditch (bottom) in feet.**

**0.5 = Safety factor constant. (1/2 foot of freeboard)**

# EXAMPLE

With an AW of 18.75, using a D7G to excavate the ditch, determine the ditch depth.

$$18.75 \text{ aw} \div 7.25' \text{ (D7 width)} + .5 \text{ (freeboard)} = 3.1' \text{ deep}$$

# PRACTICAL APPLICATION

- Trapezoidal Ditch worksheet

# EROSION CONTROL



# EROSION CONTROL METHODS

- There are several methods of erosion control.
- The desirable gradient for a ditch is between 0.5 and 2%. Ditches larger than 2% will require erosion control.
- Examples:
  - Ditch Linings
  - Check Dams



# DITCH LINING

- May be lined to prevent erosion.
- Examples:
  - Concrete
  - Asphalt
  - Rock
  - Mortor
    - Does not decrease the flow but protects the soil.  
Expensive and not always readily available
  - Grass
    - Protects the soil, slow the flow and is cheap

# EXAMPLES




# CHECK DAMS




# CHECK DAMS

- Constructed with 6-8" diameter timbers.
- Set 2' into the sides of the ditch.
- Weir notch is 6" deep and a minimum of 12" long.
- 4' of rock apron for every 1' of dam height.
- The top of the check dam should be at the high water mark, when high water mark is not visible, place check dam 1' below the top of the ditch.


SIDES SLOPE 1 HORIZONTAL  
TO 4 VERTICAL




RECTANGULAR WEIR



CIPOLLETTI WEIR



90° NOTCH WEIR



# DAM SPACING

- Will have a minimum spacing of 50 feet.
- Should be placed as far apart as possible, while achieving the desired gradient.

## Spacing Calculations:

$$S = \frac{100 (H)}{A - B}$$

**S = Dam Spacing**

**100 = Constant**

**H = Height of Dam**

**A = Present Slope**

**B = Desired Slope**

# DAM SPACING EXAMPLE

What spacing will be needed for a 4' high check dam with a 10% slope.

$$S = \frac{4 \times 100}{10 - 2}$$

$$S = 50'$$



# QUESTIONS





# CULVERTS

- Two classifications
  - Permanent (refer back to the Military Roads class)
  - Expedient
- Different types of material used
  - Corrugated metal
  - Concrete
  - Vitrified Clay (VC)
  - Polyvinyl Chloride (PVC)
  - Timber
  - Ect.

# CULVERTS

- Timber Box
  - Good workmanship
  - Large timber
  - Strong enough to support heaviest vehicle traffic
  - Minimum of 12" cover
- Corrugated Metal Pipe Culvert (CMP)
  - 8"-72" diameter
  - Shipped in 26" long half sections
  - Bolted in every hole

# CULVERTS

- Concrete pipe
  - Comes in any size
  - Comes in different shapes (circle, square, etc)
  - Overall strength
  - Smooth interior surface
  - Higher amount of water flow
  - Transportation considerations

# MAXIMUM ALLOWABLE CULVERT DIAMETER

- Permanent culverts are selected based on their diameter.
- There are two maximum diameter (Dmax) equations.
  - Fills greater than 36 inches
$$D_{max} = \frac{2}{3} \times F$$
  - Fills less than 36 inches
$$D_{max} = F - 12$$

# FILLS GREATER THAN 36"


$$D_{\max} = \frac{2}{3} \times \text{Fill}$$

$D_{\max}$  = Maximum culvert diameter in inches rounded to two decimal places.


$\frac{2}{3}$  = A constant that represents the minimum fill depth required for the maximum diameter of culvert to be calculated.

Fill = Fill depth in inches rounded to two decimal places.

# MAXIMUM ALLOWABLE CULVERT DIAMETER



# MAXIMUM ALLOWABLE CULVERT DIAMETER



# EXAMPLE

$$D_{\max} = \frac{2}{3} \times F$$

$$F = 6' \times 12'' = 72''$$

$$D_{\max} = \frac{2}{3} \times 72''$$

$$D_{\max} = 48 \text{ inches}$$



# PRACTICAL APPLICATION

- Complete the DMAX worksheet

# CULVERT MATERIALS

- Several Factors
  - Economical Diameter
  - Number of pipe required
  - Culvert Length
  - Order Length

# ECONOMICAL DIAMETER

- You want to save material.
- Put in the least amount of culverts.
- They need to equal or exceed the design area.
- Manpower requirements

# PIPES REQUIRED

- To find the most economical size, you must divide the design area by the end area of several different pipe sizes.
- Use the largest pipe that satisfies the fill and cover requirements as a starting point.
- Work your way down in size until the amount of pipes needed changes.
- Once changed, we have reached and passed our optimal design. Go back to the prior number and pipe demision.

# ECONOMICAL DIAMETER FORMULA

$$N = \frac{A_{des}}{PEA}$$

N = Number of Pipes

A<sub>des</sub> = Design Cross Section

PEA = Pipe End Area, cross sectional  
end area of culvert in ft squared

# COMMON CULVERT SIZES

Maximum Diameter (")	Cross Sectional Area (sqft)
----------------------	-----------------------------

12"	00.79 sqft
18"	01.77 sqft
24"	03.14 sqft
30"	04.91 sqft
36"	07.07 sqft
42"	09.62 sqft
48"	12.57 sqft
60"	19.64 sqft
72"	28.27 sqft

# EXAMPLE

$$N48'' = A_{des} \div A_{48}$$

$$N48'' = 17.5 \div 12.57 = 1.4 \text{ or } 2$$

$$N48'' = (2) \text{ } 48'' \text{ Pipes}$$

$$N42'' = A_{des} \div A_{42}$$

$$N42'' = 17.5 \div 9.62 = 1.8 \text{ or } 2$$

$$N42'' = (2) \text{ } 42'' \text{ Pipes}$$

$$N36'' = A_{des} \div A_{36}$$

$$N36'' = 17.5 \div 7.07 = 2.5 \text{ or } 3$$

$$N36'' = (3) \text{ } 36'' \text{ Pipes}$$

# CULVERT LENGTH

Now that we've determined that we will need (2) 42" diameter culverts, we must now calculate the culvert length. Use the following formula to do so:

$$(DL \times SL) + ROADWAY WIDTH + (DR \times SR) = CL$$

**Culvert Length**

**Note: After calculating culvert length, ensure you round up to an even number.**



# EXAMPLE

$$CL = ( 7 \times 2 ) + 22' + ( 6 \times 3 )$$

$$CL = 14' + 22' + 18'$$

$$CL = 54' + 2' \text{ ( no headwalls on the exhaust end)}$$

$$CL = 56'$$

## ORDER FORMULA


$$OL \text{ (order length)} = CL \times \# \text{ of pipes} \times 1.15 \text{ (waste)}$$

$$OL = ( 56' \times 2 ) 1.15$$

$$OL = ( 112 ) 1.15$$

$$OL = 128.8' \text{ or } 130' \text{ of pipe needed}$$

# STRUTTING






**HEADWALL**  
**L**



# EXHUA ST WITHOUT HEADWAL L









# QUESTIONS



